



Request for Quote

DUHAMEL WATER SYSTEM: WELL PUMP REPLACEMENT PRJ25029

ADDENDUM NO. 1

Issued: April 9, 2025

Closing Date: 2:00 pm Local Time, April 16, 2025

This Addendum shall be read in conjunction with and considered as an integral part of the Contract Documents; revisions supersede the information contained in the original specifications or previously issued Addendum. Price submitted shall include all items of this Addendum.

By this **Addendum No. 1**, the RFQ documents shall be amended as specified below.

Questions and Answers

Q1. Are there any pictures of inside the well cap?

A1. See picture below.



Q2. Is the 4" drop pipe steel or stainless steel?

A2. The existing drop pipe is believed to be epoxy coated steel.

Q3. Is it possible to get a picture of inside the junction box at the wellhead?

A3. See picture below.



Q4. Is the well Level transmitter existing?

A4. No, the RDCK has purchased this and will install it during this project.

Q5. “Supply and install a VFD and pressure transducer . VFD to be a Franklin Electric Cerus X-Drive 25HP or equivalent. Transducer to be a Franklin Electric Cerus-X Transducer. The RDCK’s electrician and controls contractor can make all connections/terminations into the upgraded electrical and controls”. This is a little bit confusing. Can you elaborate on the difference between us installing and your electrical and control contractor making all the connections/terminations.

A5. The RDCK is currently upgrading the electrical and controls components related to the pumphouse to ensure that the new motor/pump and VFD will function following installation. Our electrician can make all terminations from the well pump junction box back to the pumphouse unless the Bidder wants to have their electrician present during the installation and commissioning.

Q6. Can we get a timeline for your electrical and controls contractor to make all the connections/terminations into the upgraded electrical and controls.

A6. The electrical upgrades are occurring mid-April with completion by the end of April 2025.

Except as modified by Addendum No. 1 issued April 9, 2025, the Request for Quote documents for PRJ25029 shall remain unchanged.



AJ Evenson

Senior Project Manager, Regional District of Central Kootenay

- END OF DOCUMENT -